



राष्ट्रीय यूनानी चिकित्सा संस्थान
NATIONAL INSTITUTE OF UNANI MEDICINE

Kottigepalya, Magadi Main Road, Bangalore – 560 091
(An autonomous body under Ministry of Ayush, Govt. of India)
(Accredited to NABH)



Tel : 080-23584260

F.No.17-5/2024-25/Admn/NIUM/1390

Date: 25.02.2025

To,

Sub: Inviting Quotation for Civil repair works in Canteen Complex at NIUM, B'lore-reg:

Sir,

With reference to the subject, cited above sealed quotations are invited from reputed firms/contractors for civil repair works in the Canteen complex of this Institute.

The specification/measurement is below

Sl. No.	Description	Qty	Unit	Price per Sq.ft	Amount in Rs.
1	Dismantling of existing old concrete floor(Rain water pathway) cutting the disturbing roots of tree and formation with soil filling, etc.,	260	SFT		
2	Providing and laying of 4'' Thick concrete flooring in mixing of 1:2:4 using with 20mm and down size aggregates and single washed M Sand and 53 grade cement and neat finishing on top using with 1:4 Cement mortar with required slope for flow out the rain water(Canteen back side and center path way)	260	SFT		
3	Providing and constructing non load bearing wall with cement concrete solid blocks with compressive strength not less than 35kg/sqm block size of 40X15X20 cms for drainage walls and other works and plastering cement mortal using 1:4 ratio including cost of all materials, labour, curing complete as per specifications	150	SFT		
4	Providing and fixing of Drainage Chamber covers wherever necessary and upgrading the chamber walls	10	No's		
5	Replacing of existing damaged Mangalore roof tiles with good quality including labour charges	30	No's		
6	Cleaning existing Mangalore tile roof area	Lumpsum	Lumpsum		
7	Providing and fixing of Cobble stones pave floor wherever required of existing type	50	SFT		
8	Repair of existing damaged aluminium doors including necessary fittings, screw, etc.,	3	No's		
9	Remove of existing broken glass and providing and fixing of plain glass of existing type	1	No		
10	Providing and fixing of 2.5'' Plumbing line with connection (new line) for canteen washing area	Lumpsum	Lumpsum		
11	Construction of small way on two sides replacement of water pipe connected on two sides to avoid the rain water on the canteen area	Lumpsum	Lumpsum		
12	Cover of drainage area using with heavy duty concrete slabs for small way	60	SFT		
13	Construction of gas cylinder storage in the outside kitchen area of canteen using with MS angle and MS mesh once coat primer etc., Upper side puff sheet and cover with polycarbonate sheet (Size 10'X6'X1'6'')	98	SFT		


14	Replacement of existing damaged floor tiles at canteen washing utensil area of existing type	Lumpsum	Lumpsum		
15	Providing and fixing of MS racks for storage of cooking materials size (1) 7'X7'X2' and (2) 9'X7'X2' with three shelves	112	SFT		
				Total in Rs.	
				GST charges	
				Grand total in Rs.	

Terms and conditions

1. The firm should mention the GST No. properly and submit the copy of GST registration certificate
2. The firm may mention the time required for completion of the above work
3. The firm may visit the Institute to check the above details before quoting the rates
4. The firm may mention the GST/taxes separately if applicable
5. The firm should arrange his own people and own tools for the above works at this Institute
6. Any sort of damages caused during the work the firm is wholly & solely responsible.
7. For delay in completing the work following Penalty shall be imposed
 - a. For delay of five days 5% of the billed amount
 - b. For delay of 6-10 days 10% of the billed amount
 - c. For delay of 11-15 days 15% of the billed amount
 - d. For delay of 16 -20 days 20% of the billed amount and there after no payment will be released
8. The quotations received after due date will not be considered
9. The firms shall quote their rates as per the specification invited in the quotation by the Institute
10. Tampering/alterations made in the rates quoted will be not be considered
11. Electricity and Water charges if any utilized by the Institute the proportionate deductions will be deducted in the bill of LI
12. The sealed quotation covers has to be compulsorily fully superscribed as Civil repair works in Canteen Complex at NIUM, B'lore
13. If the sealed quotation cover is not superscribed in the full the same will not be considered
14. If any dispute rise the decision of Director, NIUM is final and binding

The quotations may be submitted to this office by post/hand on or before 10.03.2025, by super scribing "Civil repair works in Canteen complex at NIUM, B'lore".

भवदीय/Yours faithfully,



(सुरेश/Suresha)

लेखाअधिकारी/Accounts officer

Distribution:

1. Website I/c for information and request to upload the above quotation in the Institute website
2. Canteen Committee for information
3. Concerned file
4. Guard file